

投 标 总 价

招 标 人：_____

工 程 名 称：2026 年禹州市境内标线施划工程

投 标 总 价 (小写)： 3594444.2 _____

(大写)： 叁佰伍拾玖万肆仟肆佰肆拾肆元贰角 _____

投 标 人：_____



(单位盖章)

法定代表人

或其授权人：_____

吴纪生

(签字或盖章)

编 制 人：_____



(造价工程师签字盖章专用章)

时 间： 2026 年 9 月 17 日

养护工程预算表

建设项目名称：2026年禹州市域内标线施划工程
编制范围：2026年禹州市域内标线施划工程

分项编号	工程或费用名称	单位	数量	金额(元)	技术经济指标	各项费用比例(%)	备注
1	第一部分 建筑安装工程费	公路公里		3578620.45		99.56	建设项目路线总长度(主线长度)
101	临时工程	公路公里		57324.35		1.59	
10104	临时安全设施	处		57324.35		1.59	
1010401	养护施工安全设施设置(202个路口)	处	151	57324.35	379.63	1.59	
107	交通工程及沿线设施	公路公里		3462833.96		96.34	
10701	拆除旧设施	公路公里		96763.52		2.69	
1070101	清除路口原有磨损标线	m ²	4797	96763.52	20.17	2.69	
10702	交通安全设施	公路公里		3366070.44		93.65	
1070202	重建或新增	Km		3366070.44		93.65	
107020204	热熔标线	m ²	87080	3019739.23	34.68	84.01	
107020205	常温冷漆标线	m ²	22978	346331.21	15.07	9.64	
110	专项费用	元		58462.14		1.63	
11002	安全生产费	元		58462.14		1.63	
2	第二部分 土地征用及拆迁补偿费	公路公里					
3	第三部分 养护工程其他费	公路公里		15823.75		0.44	
301	项目管理费	公路公里					
303	项目前期工作费	公路公里					
306	工程保险费	公路公里		15823.75		0.44	
4	第四部分 预备费	公路公里					
5	第一至四部分合计	公路公里		3594444.2		100.00	
6	第五部分 贷款利息	公路公里					
7	公路养护工程总费用	公路公里		3594444.2		100.00	



复核:

编制:

表A.0.2-6 人工、主要材料、施工机械台班数量汇总表

建设项目名称：2026年禹州市境内标线施划工程
编制范围：2026年禹州市境内标线施划工程

代号	规格名称	单位	单价(元)	总数量	分项统计							场外运输损耗	
					临时工程	交通工程及 沿线设施					辅助生产	%	数量
1001001	人工	工日	108.85	3680.99	83.05	3597.94							
1051001	机械工	工日	108.85	1021.52	66.44	955.08							
3003002	汽油(93号)	kg	8.33	26547.567	1735.413	24812.154							
5009003	标线漆(常温型)	kg	14.53	11259.22		11259.22							
5009007	底油	kg	11.57	14420.448		14420.448							
5009008	热熔涂料	kg	4.8	294051.744		294051.744							
6007003	反光玻璃珠(JT/T280-1995 1、2号(A类))	kg	3.33	60001.603		60001.603							
6007023	锥形交通标志	个	26.8	270.743	270.743								
6007809	施工标志牌	块	239.32	0.302	0.302								
6007810	警告标志牌	块	252.99	0.302	0.302								
6007811	禁令标志牌	块	270.94	0.302	0.302								
7801001	其他材料费	元	1	41756.602		41756.602							
8003070	热熔标线设备	台班	801.32	301.297		301.297							
8003074	标线清除机	台班	447.1	90.663		90.663							
8007002	3t以内载货汽车	台班	405.43	77.473	66.44	11.033							
8007003	4t以内载货汽车(CA10B)	台班	475.58	250.79		250.79							
8099001	小型机具使用费	元	1	36861.185		36861.185							



编制:

复核:

表A.0.2-7 建筑安装工程费计算表

建设项目名称：2026年禹州市境内标线施划工程
编制范围：2026年禹州市境内标线施划工程

第 1 页 共 1 页

03表

序号	分项编号	工程名称	单位	工程量	定额直接费(元)	定额设备购置费(元)	直接费(元)				措施费	企业管理费	规费	利润(元)	税金(元)	金额合计(元)		
							人工费	材料费	施工机械使用费	合计						合计	单价	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
1	101	临时工程	公路公里		49553.3		9039.99	7486.41	26936.77	43463.18				5451.12	3676.86	4733.2	57324.35	
2	10104	临时安全设施	处		49553.3		9039.99	7486.41	26936.77	43463.18				5451.12	3676.86	4733.2	57324.35	
3	1010401	养护施工安全设施设置(202个路口)	处	151	49553.3		9039.99	7486.41	26936.77	43463.18				5451.12	3676.86	4733.2	57324.35	379.63
4	107	交通工程及沿线设施	公路公里		2604097.99		391635.77	1983451.36	442575.95	2817663.08				166024.75	193224.07	285922.07	3462833.97	
5	10701	拆除旧设施	公路公里		70122.46		26107.67		45008.71	71116.38				12454.4	5203.09	7989.65	96763.52	
6	1070101	清除路口原有磨损标线	m2	4797	70122.46		26107.67		45008.71	71116.38				12454.4	5203.09	7989.65	96763.52	20.17
7	10702	交通安全设施	公路公里		2533975.53		365528.1	1983451.36	397567.24	2746546.69				153570.35	188020.98	277932.42	3366070.45	
8	1070202	重建或新增	Km		2533975.53		365528.1	1983451.36	397567.24	2746546.69				153570.35	188020.98	277932.42	3366070.45	
9	107020204	热熔标线	m2	87080	2261011.6		272985.35	1819854.9	387227.14	2480067.38				122568.53	167767.06	249336.27	3019739.23	34.68
10	107020205	常温冷漆标线	m2	22978	272963.93		92542.75	163596.47	10340.1	266479.31				31001.82	20253.92	28596.16	346331.21	15.07
11	110	专项费用	元							58462.14							58462.14	
12	11002	安全生产费	元							58462.14							58462.14	

综合费率计算表

养护工程项目名称：2026 年禹州市境内标线施划工程

编制范围：2026年禹州市境内标线施划工程

第 1 页 共 1 页

3-04表

序号	工程类别	措施费 (%)				企业管理费 (%)	规费 (%)					
		基本措施费用	施工进出场费	行车干扰施工增加费	综合费率		养老保险费	失业保险费	医疗保险费	工伤保险费	住房公积金	综合费率
1	2	3	4	5	6	7	8	9	10	11	12	13
01-1	路基-土石方					4.025	16	0.7	7.3	1	8.5	33.5
01-2	路基-构造物					5.029	16	0.7	7.3	1	8.5	33.5
02	运输					2.653	16	0.7	7.3	1	8.5	33.5
03	路面					4.077	16	0.7	7.3	1	8.5	33.5
04	隧道					5.271	16	0.7	7.3	1	8.5	33.5
05	桥梁					6.915	16	0.7	7.3	1	8.5	33.5
06	商混及外购件					8.396	16	0.7	7.3	1	8.5	33.5
07	钢材及钢结构					3.44	16	0.7	7.3	1	8.5	33.5




编制:

复核:

综合费用计算表

序号	工程名称	措施费 (元)				企业管理费 (元)	规费 (元)					
		基本措施费用	施工进出场费	行车干扰施工 增加费	综合费用		养老保险 费	失业保险 费	医疗保险费	工伤保险费	住房公积金	综合费用
1	2	3	4	5	6	7	8	9	10	11	12	13
1	养护施工安全设施设置(202个路口)					1837.48	2366.83	103.55	1079.87	147.93	1257.38	4955.56
2	清除路口原有磨损标线					2889.17	10359.52	453.23	4726.53	647.47	5503.5	21690.25
3	热熔标线					106901.12	81288.97	3556.39	37088.09	5080.56	43184.77	170198.78
4	常温冷漆标线					11128.74	14806.84	647.8	6755.62	925.43	7866.13	31001.82
5	合计:					122756.51	108822.17	4760.97	49650.11	6801.39	57811.78	227846.42





编制:

复核:

表A.0.3-1 分项工程预算计算数据表

建设项目名称：2026年禹州市境内标线施划工程 编制范围：2026年禹州市境内标线施划工程									
标准定额库版本号： 校验码： 第 1 页 共 1 页 21-表									
分编号/定额 代号/工料机代号	项目、定额或工料机的名称	单位	数量	输入单价	输入金额	分项组价类型 或定额子目取费类别	定额调整情况或分项算式		
1	第一部分建筑安装工程费	公路公里			3578620.45				
101	临时工程	公路公里			57324.35				
10104	临时安全设施	处			57324.35				
1010401	养护施工安全设施设置(202个路口)	处	151	379.63	57324.35				
借[豫2021普养预]5-2-4-1按	临时定点养护维修(不设移动式标志车)	1处	151	379.63	57324.35	06.构造物 I	定额*1.1;		
107	交通工程及沿线设施	公路公里			3462833.96				
10701	拆除旧设施	公路公里			96763.52				
1070101	清除路口原有磨擦标线	m2	4797	20.17	96763.52				
借[豫2021普养预]5-1-12-3	机械清除路面标线	100m2	47.97	2017.17	96763.52	06.构造物 I			
10702	交通安全设施	公路公里			3366070.44				
1070202	重建或新增	Km			3366070.44				
107020204	热熔标线	m2	87080	34.68	3019739.23				
借[豫2021普养预]5-1-12-7按	补划沥青混凝土路面反光型热熔标线	100m2	870.8	3467.78	3019739.23	06.构造物 I	定额*0.72;		
107020205	常温冷漆标线	m2	22978	15.07	346331.21				
借[豫2021普养预]5-1-12-4	人工补划常温普通标线	100m2	229.78	1507.23	346331.21	06.构造物 I			
110	专项费用	元			58462.14				
11002	安全生产费	元			58462.14				
2	第二部分土地征用及拆迁补偿费	公路公里			15823.75				
3	第三部分养护工程其他费	公路公里							
301	项目管理费	公路公里							
303	项目前期工作费	公路公里			15823.75				
306	工程保险费	公路公里							
4	第四部分预备费	公路公里			3594444.2				
5	第一至四部分合计	公路公里							
6	第五部分贷款利息	公路公里							
7	公路养护工程总费用	公路公里			3594444.2				



编制： 复核：

表A.0.2-14 人工、材料、施工机械台班单价汇总表

建设项目名称：2026年禹州市境内标线施划工程
编制范围：2026年禹州市境内标线施划工程

序号	名称	单位	代号	预算单价 (元)	备注
1	人工	工日	1001001	108.85	
2	机械工	工日	1051001	108.85	
3	汽油93号	kg	3003002	8.33	
4	标线漆常温型	kg	5009003	14.53	
5	底油	kg	5009007	11.57	
6	热熔涂料	kg	5009008	4.8	
7	反光玻璃珠J/T280--1995 1、2号(A类)	kg	6007003	3.33	
8	锥形交通标志	个	6007023	26.8	
9	施工标志牌	块	6007809	239.32	
10	警告标志牌	块	6007810	252.99	
11	禁令标志牌	块	6007811	270.94	
12	其他材料费	元	7801001	1	
13	热熔标线设备	台班	8003070	801.32	
14	标线清除机	台班	8003074	447.1	
15	3t以内载货汽车	台班	8007002	405.43	
16	4t以内载货汽车CA10B	台班	8007003	475.58	
17	小型机具使用费	元	8099001	1	



编制:

复核:

表A.0.3-2分项工程预算表

编制范围: 2026 年禹州市境内标线施划工程
分项目编号: 107020204

第3页共4页

单价: 34.68

数量: 87080

单位: m²

工程名称: 热熔标线

范围: 2020 年 10 月
编号: 107020204

[illegible]

编制:

复核:

表A.0.3-2分项工程预算表

编制范围：2026年禹州市境内标线施工工程															21-2表												
分项目编号：107020205															第4页共4页												
工程名称：常温冷漆标线															单价：15.07												
单位：m2															数量：22978												
工程 项目															路面标线												
工程 细 目															人工补划常温普通标线												
定 额 单 位															100m2												
工程 数 量															229.78												
定 额 表 号															借豫2021普养预5~1~12~4												
工、料、机名称															单位	单价	定额	数量	金额(元)	定额	数量	金额(元)	数量	金额(元)	数量	金额(元)	
1001001															人工	工日	108.85	3.7	850.186	92542.75				850.186	92542.75		
5009003															标线漆常温型	kg	14.53	49	11259.22	163596.47				11259.22	163596.47		
8099001															小型机具使用费	元	1	45	10340.1	10340.1				10340.1	10340.1		
9999001															定额基价	元	1	1188	272964	272964				272964	272964		